## ENGINEERED PERFORMANCE STANDARDS

BOOK NUMBER - 08

# MOVING AND RIGGING



## TABLE OF CONTENTS

## BOOK 08

CHAPTER	DESCRI	PTION	PAGE
010	CRANE OPERATIONS	- Material and Equipment.	1
020	CRANE OPERATIONS	- Heating, Ventilating, Air Conditioning	5
030	CRANE OPERATIONS	Items, Artillery Targets Communication Tower Antennas.	7
040	CRANE OPERATIONS	- Marine Rigging.	8
050	CRANE OPERATIONS	- Tugboat and Docking Equipment	10
060	FURNITURE MOVING	- Minor and major items	13
070	REEVING	- Cables.	16
080	SCAFFOLDING	- Assemble and Disassemble.	18
090	SHOP OPERATIONS	-	20
100	WEIGHT CAPACITY TESTING	- Cranes, forklift trucks.	22
110	DRIVE-ON TRAILER LOADIN	G/UNLOADING - Folding gooseneck	24
120	BACKHOE OPERATIONS	- Concrete street barriers	25

## EPS SUPPLEMENTAL DATA CRAFT DELAY ALLOWANCE, JOB PREPARATION

CRAFT	JOB PREP	CRAFT DELAY SINGLE	
BOILER WORK	.4	23	33
CARPENTRY - GENERAL	.3	15	20
CARPENTRY - ROOFING	.6	20	25
COOLING/VENT/REFER.	.3	15	18
ELECTRICAL & ELECTRONIC	.3	16	20
HAZARDOUS WORK (ADD TO JP)	.2		
HEATING	.3	17	21
JANITORIAL	.3	11	13
MACHINE SHOP	.3	23	24
MACHINE REPAIR	.4	28	36
MASONRY - GENERAL - W/ PURCH. CONC.	.4	15 19	20 22
MOVING AND RIGGING	.3	28	40
PAINT - GENERAL - SPRAY	.2	16 17	17 19
PEST CONTROL	.3	14	17
PIPEFITTING - INTERIOR - EXTERIOR	.3	15 18	20 25
PLUMBING - INTERIOR - EXTERIOR	.3	17 15	20 20
ROADS & GRNDS - GENERAL - LABORERS	.3	16 15	20 20
SHEETMETAL	.3	15	20
STRUC IRON & WELD - FIELD - SHOP	.3	17 17	20 22
TRACKAGE	. 4		22
WHARFBUILDING	.5	24	32

: Crane Operations; Material & Equipment : Includes: time to load, relocate, unload, move, raise & : lower, install or remove, relocate, raise & position, pull or : load various types of material & equipment. (1)Crawler crane; : (2)House trailer; (3)Steel plate; (4)Cylindrical object; (5)Steel : matting/metal; (6,9)Heavy machinery/equipment; (7)Loaded plat-: form; (8) Tree; (10) Tank; (11) Bleacher; (12) Personnel basket; : (13)Transformer; (14)Medium weight equipment; (15)Motor-generator

#### TASK TIME STANDARDS LISTING

вт	001	Crawler crane 15 ton- UNLOAD from flat car (15 ton). rmv-cribbing,chocks,addl parts
вт	002	House trailer - RELOCATE; load&unload to flatbed truck trailer & piers using sling
вт	004	Steel plate to 5 ton- PROCURE from stock area; load, unload, sling using dunnage, lowboy & crane.
вт	005	Cylindrical object - MOVE to a new location. 8ft dia.x 50ft 8ftx50ft long, six tons.
вт	007	Steel matting/metal - LOAD or UNLOAD bundles to lowboy truck with sling using dunnage.
вт	023	Heavy machinery/equipment- RELOCATE using block & tackle, jacks & roller skids.
вт	059	Loaded platform - RAISE & POSITION between two poles-using crane
вт	056	Tree - PULL with crane, position crane & lowboy
		booley/bool 2 atip GKOIMI 2 GKOI to
вт	024	at LOAD & UNLOAD site & load/unload Heavy machinery/equipment- MOVE using block & tackle, jacks,
	024 061	Heavy machinery/equipment- MOVE using block & tackle, jacks, skids, crane & lowbed Tank, 4ftdia x 15ft - 3,000 lbs; MOVE from bldg to bldg using
вт		Heavy machinery/equipment- MOVE using block & tackle, jacks, skids, crane & lowbed Tank, 4ftdia x 15ft - 3,000 lbs; MOVE from bldg to bldg using dolleys, jacks, crane, lowboy. Iron bleacher section- 20ftwide x 32ft; RELOCATE, position lowboy
BT BT	061	Heavy machinery/equipment- MOVE using block & tackle, jacks, skids, crane & lowbed Tank, 4ftdia x 15ft - 3,000 lbs; MOVE from bldg to bldg using dolleys, jacks, crane, lowboy.
BT BT	061 064	Heavy machinery/equipment- MOVE using block & tackle, jacks, skids, crane & lowbed Tank, 4ftdia x 15ft - 3,000 lbs; MOVE from bldg to bldg using dolleys, jacks, crane, lowboy. Iron bleacher section- 20ftwide x 32ft; RELOCATE, position lowboy crane, load & unload.
BT BT	061 064 170	Heavy machinery/equipment- MOVE using block & tackle, jacks, skids, crane & lowbed Tank, 4ftdia x 15ft - 3,000 lbs; MOVE from bldg to bldg using dolleys, jacks, crane, lowboy.  Iron bleacher section- 20ftwide x 32ft; RELOCATE, position lowboy crane, load & unload.  Personnel basket - RAISE & LOWER using crane.
BT BT BT	061 064 170	Heavy machinery/equipment- MOVE using block & tackle, jacks, skids, crane & lowbed Tank, 4ftdia x 15ft - 3,000 lbs; MOVE from bldg to bldg using dolleys, jacks, crane, lowboy.  Iron bleacher section- 20ftwide x 32ft; RELOCATE, position lowboy crane, load & unload.  Personnel basket - RAISE & LOWER using crane. Transformers - REMOVE & INSTALL from power line pole,50ft

BT 001 Unload crawler crane from flat car (15 ton).

Includes: rmv- wire rope tie downs, cribbing & chocks; sling clam bucket, dragline bucket, boom section & 3 boxes of spare parts; raise, position & release loads; position crane; move crane off railroad car approximately 50 yards.

002.09806 hours per hrs per crane

BT 002 Relocate house trailer.

Includes: position crane & lowbed truck at load & inload points; sling & unsling trailer; place & remove dunnage on truck, load & unload & position 6 concrete piers; raise ,lower, position, release trailer.

001.57416 hours per house trailers

BT 004 Procure one steel plate (up to 10,000 pounds) for fabrication from stock area and unload to lowbed truck.

Includes: position crane & lowbed truck at load &unload point; attach & remove sling; raise, position & release load; set dun nage on lowbed truck; move 2 plates to select desired plate.

001.46466 hours per plates

BT 005 Move cylindrical object, 8' diameter x 50' long, to new location.

Includes: position crane & lowbed, sling & unsling load;
raise, position & release, load; lash & unlash load (chain binders; place dunnage to set load & remove.

001.36290 hours per objects

BT 007 Load or unload bundles of steel matting or sheet metal using dunnage.

Includes: position crane & lowbed at load & unload points; place dunnage and remove; sling & unsling bundles; raise, position & release loads at load & unload points.

000.50842 hours per JOB SETUP TIME

000.47433 hours per bundles

BT 023 Relocate heavy machinery or equipment in shop using block and tackle, jacks and roller skids.

Includes: raise heavy part with hydrolic jacks & blocking, place on dollies or roller; pull heavy part on average of 50' using block & tackle.

001.44168 hours per items

BT 059 Raise and position platform, elevated with load, between two poles.

Includes: position crane to basket, sling & unsling basket, attach & remove tag & safty lines; raise position & lower; slin & unsling platform & cradle, 2 times.

3

001.60080 hours per platforms

BT 056 Pull tree with crane, load on truck and dispose of at dump.

Includes: position crane at load & unload points; sling & unsling; raise position release 2 times; lash & unlash on truck; pull tree to & from truck;

001.44380 hours per JOB SETUP TIME

000.00200 hours per feet each tree is pulled

BT 024 Move heavy machinery or heavy equipment to a new location using block and tackle, jacks, skids, crane and lowbed.

Includes: relocate machine using block & tackle jacks & rolle skids; position crane, lowbed, load & unload; sling unsling; lash & unlash load.

002.66645 hours per items

BT 061 Move tank, 4' diameter x 15' long, approximately 3,000 pounds, out of building into another building.

Includes: place tank on dollies with jacks; roll out of building; sling & unsling; position crane & truck at load & unload site; raise position and release at load & unload site; lash & unlash to truck.

002.98819 hours per tanks

BT 064 Relocate structural iron bleacher seat section, approximately 20' wide x 32' long.

Includes: dis & assemble tie rods; position crane & truck at load & unload site; sling & unsling front & rear sections & upright supports at sites; raise position release loads; lash & unlash loads.

004.09250 hours per bleacher seat sections

BT 170 Raise and lower personnel basket with crane, up to 50'.

Includes: position crane; attach & remove sling; raise position and release load; additional crane travel.

000.03646 hours per JOB SETUP TIME

000.36388 hours per locations

BT 139 Install or remove transformers from 50' high platform on power line pole.

> Includes: position crane, climb up and down pole, sling & unsling transformers, raise position and release load.

000.17008 hours per poles

000.31198 hours per transformers per pole

BT 143 Load or unload, medium weight .5 to 10 tons, 30' to 90' long, pieces of equipment from trailer or railroad car to ground or surface of water using a mobile crane.

> Includes: position crane, lash & unlash load, chain & binders attach & remove slings; raise, position, & release load.

000.17008 hours per JOB SETUP TIME

000.35818 hours per items

BT 168 Position motor generator units into precise location within vault using mobile crane.

> Includes: position crane; attach & remove sling; raise position and release load.

000.17008 hours per JOB SETUP TIME

000.23026 hours per generators

:

PAGE - Heating, Ventilating, Air Conditioning Items, Artillery Targets.

Crane Operations: Relocate- HVAC components, Artillery Targets

Tasks Include: time to load & place, remove & install, move from one location to another exact location, various types of heating, ventilating, and air conditioning items and/or

artillery targets.

#### TASK TIME STANDARDS LISTING

rmv or instl rooftop.... A/C EVAPORATIVE UNIT to 7500 cfm ea. BT 055

rmv or instl rooftop.... HVAC MAJOR COMPONENTS one location BT 138

one location BT 141 rmv or instl rooftop.... FILTERS LARGE

BT 113 move to exact location... ARTILLERY TARGETS, of concrete block

BT 114 more to exact location... ARTILLERY TARGETS, of steel

## EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

BT 055 Load and place air conditioning units on roof, evaporative type, up to 7500 CFM each.

> Includes: position 5 ton crane at load & unload points, sling & unsling; raise, position & release load.

000.50842 hours per JOB SETUP TIME

000.46052 hours per air conditioning units

Remove or install major HVAC items located on rooftop. Items BT 138 include air handling unit, cooling tower, water distiller, and air conditioning compressor.

> Includes: position crane & lowbed truck at load & unload points, walk thru building to roof & return, sling & unsling units, raise position and release unit.

000.56842 hours per JOB SETUP TIME

000.46052 hours per items

Remove or install large filters - for large air conditioning BT 141 units, centrifugal blowers, rooftop ventilators. Filters up to 400 pounds each.

Includes: position crane, walk thru building to roof & return rig chain fall & hoist to overhead beam & remove, rmv & install screws, move filters sling & hoist, raise & hoist filters &lowe

000.23008 hours per JOB SETUP TIME

000.62088 hours per filters

BT 113 Move concrete blocks from one range location to another exact location using truck crane and lowbed truck.

Includes: position crane & lowbed truck at range block; attac sling to crane hook; attach & detach sling to bloch; raise position & release load; and go through same procedure at new site to unload lowbed truck of range block.

000.93106 hours per blocks

BT 114 Move steel artillery targets from one range location to another exact location using truck crane.

Includes: position crane at steel artillery target; raise target; position crane & target at concrete block; set target in exact location.

000.54605 hours per targets

Crane Operations: Communications Tower Antennas
Tasks Include: time to install or remove, disassemble & erect.

#### TASK TIME STANDARDS LISTING

- BT 135 Transmitter disks.....INSTALL or REMOVE.
- BT 136 Communication tower sections....DISASSEMBLE
- BT 137 Communication tower sections....ERECT

#### EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

BT 135 Install or remove high or low frequency transmitter disks to or from a communications tower (one winch operator, two signal one tagline operator, two riggers).

Includes: climb tower, raise tools, connect & disconnect cable, catwalk, lugall jack, jib pole, dick, hoist to position & secure disk to tower.

011.34304 hours per disks

BT 136 Disassemble sections of communications tower (two drivers, one signalman, one rigger).

Includes: position crane, climb tower, raise & lower tools, raise boom to section, attach slings, disassamble section bolts lower section to ground.

000.71752 hours per JOB SETUP TIME

003.52744 hours per sections

BT 137 Erect communications tower sections (two drivers, two rigger one signalman).

Includes: position crane & winch truck near tower, attach winch cable & sling to tower section, climb & raise & lower tools, raise tower section 30', assemble section bolts.

000.97190 hours per JOB SETUP TIME

007.94840 hours per sections

- Marine Rigging.

: Crane Operations: Marine Rigging : Tasks Include: time to load or unload or exchange marine rigging : material or equipment. (1)Cargo container, palletized load, flat : steel plates, 30' steel beam; (2)Stacked steel plate; (3)Diesel : engine; (4)3000 gal. asphalt tank; :

#### TASK TIME STANDARDS LISTING

BT 111 Portal crane -LOAD OR UNLOAD ITEMS/FREIGHT 1 to 7 locations 30ft apart ship to dock 18ft high

BT 140 Floating crane -LOAD OR UNLOAD ITEMS steel plate 65T ea from RR CAR to BARGE at the dock

BT 149 Floating crane -EXCHANGE DIESEL ENGINED

BT 146 Floating crane -LOAD OR UNLOAD 3,000 GALLON ASPHALT TANK

EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

BT 111 Load or unload(ship to dock): cargo containers to or from raised positions (fork truck or dunnage); palletized loads (strapped) to ship from pier (15' elevation); flat steel plates (4' x 20' 1") from ship to pier using plate clamps and crane; 30' steel beams from ship to pier.Incls:position crane sling raise pos re M&R crane portal unload ship to dock 18' high.

000.17008 hours per JOB SETUP TIME

000.23026 hours per items

000.01500 hours per locations

BT 140 Load or unload stacks of steel plates (25 to 65 tons per stack) from rail road car to barge using floating crane.

Includes: position crane, attach slings to load & dunnage, raise position & release load, position dunnage under load.

000.17008 hours per JOB SETUP TIME

000.26479 hours per stacks

BT 149 Exchange diesel engines on portal using a floating crane (does not include moving of crane by tugboat).

Includes: position crane; attach & remove sling to crane cab twice, and to each diesel engine once; raise position & release loads.

000.54556 hours per diesel engines

BT 146 Load or unload one 3,000 gallon asphalt tank from barge to deck of ship using floating crane (does not include maneuvering of crane by tugboat).

Includes: position crane; attach & remove sling from tank;
raise position & release load.

9

000.40034 hours per tanks

: Crane Operations- Tugboat & Docking Equipment : Tasks include time to load or unload, load & unload, install : & remove, remove, move, & place or remove tugboat & : docking equipment. (1,2,3,4,5,6,7,8)Fender; (9)Camel; (10)Brow; :

#### TASK TIME STANDARDS LISTING

- BT 159 Crane Truck- STEEL FENDER remove from yard derrick
- BT 160 Crane Truck- STEEL FENDERS remove & install from yard derrick
- BT 161 Crane Truck- BOW or STERN FENDERS load OR unload to&fromFLATBED
- BT 162 Crane Truck- BOW or STERN FENDERS load & unload to&from FLATBED
- BT 163 Crane Truck&Forklift- FENDERS move to rigging loft
- BT 164 Crane Truck- FENDERS install or remove to TUGBOAT
- BT 166 FENDERS- remove from water and place on fork truck.
- BT 167 Tugboat bow or stern FENDERS- install or remove.
- BT 097 Yard Derrick- CAMEL remove from water with yard derrick
- BT 104 Crane Portal- BROW place or remove using portal crane.

#### EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

\_\_\_\_\_

BT 159 Remove steel fenders from yard derrick using truck crane (driver and signalman).

Includes: position crane near yard derrick; raise & lower boo; hook and unhooksteel fender; hold fender for cutting (process time); lift and aside fender to yard.

000.46600 hours per fenders

BT 160 Remove and install rubber fenders from derrick using truck crane (driver and signalman).

Includes: position crane near yard derrick; raise & lower boo; hook & unhook rubber fender; hold fender for bolt removal; lift & aside fender to yard; hold new fender in place for drilling bolt holes; hold fender in place for bolt installation

000.69560 hours per fenders

BT 161 Load or unload bow or stern fenders at storage yard from/to flatbed trailer.

Includes: position load & flatbed; attach or remove crane hook; raise position & release load; lash or unlash load to trailer.

000.25421 hours per JOB SETUP TIME

000.21039 hours per fenders

\_\_\_\_\_

BT 162 Load and unload bow or stern fenders at storage yard from/to flatbed trailer.

Includes: position load & flatbed; attach & remove crane hook raise position & release load; lash & unlash load to trailer average 3 items - this whole proceedure twice.

000.50842 hours per JOB SETUP TIME

000.42076 hours per fenders

BT 163 Move fender to/from storage area to rigging loft.

Includes: position crane; attack & remove crane hook; raise position & release load; transport fender with fork lift; position forklift.

000.17298 hours per JOB SETUP TIME

000.23195 hours per fenders

BT 164 Install or remove tugboat side fenders from/to dockside flatbed trailer.

Includes: position crane; install & remove shackles & bolts; attach & remove crane hook; raise position & release load; position flatbed trailer; lash & unlash load to trailer(average 3 items)

000.25421 hours per JOB SETUP TIME

000.28559 hours per fenders

BT 166 Remove fenders from water and place on fork truck on pier.

Includes: position crane & forklift truck; raise position release load; attach & release slings.

000.17298 hours per JOB SETUP TIME

000.23026 hours per fenders

BT 167 Install or remove on tugboat, bow or stern fenders.

Includes: position crane; install or remove shackles & bolts; attach and remove crane hook; raise position release loads; lash and unlash load to trailer (average 3 items); position flatbed trailer.

000.25421 hours per JOB SETUP TIME

000.51119 hours per fenders

BT 097 Remove camel from water with yard derrick to set on forklifts for transport to repair yard.

Includes: attach with slings& hooks to 4 padeyes on camel; raise camel, lower, position & set on forklift & release; process time, position forklift to receive camel.

000.79607 hours per camels

BT 104 Place or remove brow to dockside barge using portal crane.
Includes: position crane; attach & release sling; raise,
position & release load; additional crane travel.

000.47534 hours per brows

: Furniture Moving : Minor items include chairs, small tables, boxes, wastepaper : baskets, typewriters, and any hand carried office furniture. : Major items include desks, large tables, file cabinets, : bookshelves, copier machines, small computer consoles and : conference tables. Removable obstructions include legs, stops, : : desk legs, etc. Using a crane to move major items to a : different floor or level utilizing exterior landings. Use a : crane and/or lowbed truck to move major items. (1,4)Minor items; : (2,3,5,6,7,8,9,10)Major items; (11)Removable obstructions;

#### TASK TIME STANDARDS LISTING

	028	Minor it				same build	-	
BT	029	Major it	ems- move	to new	location	same build	ing, on th	he same
							floor	or level.
BT	030	Major it	ems- move	to new	location	same build	ing, on a	different
					floor o	r level, u	sing a sma	all crane.
BT	031	Minor it	ems- move	to new	location	different :	building,	any floor
BT	032	Major it	ems- move	to new	location	different :	building,	first
						floor, a	crane is	not used.
BT	047	Major it	ems- move	to new	location	different :	building,	a crane
						to be us	ed at ONE	location.
BT	048	Major it	ems- move	to new	location	different :	building,	a crane
						to be us	ed at TWO	locations
BT	049	Major it	ems- move f	rom wan	rehouse to	office bu	ilding; f	irst floor
BT	050	Major it	ems- move f	rom wan	rehouse to	office bu	ilding; u	pper floor
вт	033	Major it	ems- measur	e for o	clearance.			
BT	034	Removabl	.e obstructi	lons- di	isassemble	or assemb	le.	

BT 028 Move minor items to new location in the same building. Minor items include chairs, small tables, boxes, wastepaper baskets, typewriters and any hand carried furniture.

Includes: hand carry minor items to new location.

000.03453 hours per items

BT 029 Move major items to new location on the same floor of a building. Major items include desks, large tables, file cabinets bookshelves, copier machines, small computer consoles, conferenc tables

Includes: move major items to new location (2 men).

000.10359 hours per items

BT 030 Move major items to a different level in the same building using a small crane. Major items include desks, large tables, fil cabinets, bookshelves, copier machines, small computer consoles conference tables.

Includes: use of small crane same building different level; sling and unsling; raise, position, release load.

000.01500 hours per JOB SETUP TIME

000.38531 hours per items

BT 031 Move minor items to new location in a different building. Minor items include chairs, small tables, boxes, wastepaper baskets, typewriters, and hand carried office equipment

Includes: move minor items to & from truck to new location (hand carry furniture to different building)

000.06906 hours per items

BT 032 Move major items from ground floor of one building to ground floor of another building using truck only. Major items include desks, large tables, file cabinets, bookshelves, copier machine small computer consoles, conference tables

Includes: 2 men hand carry furniture ground floor to ground floor& position truck at 2 locations.

000.16826 hours per JOB SETUP TIME

000.10359 hours per items

BT 047 Move major items from 1st & upper floor of one location to first or upper floor of another location, using a crane at one locatio & truck at two locations. Major items include desks, large table , file cabinets.

Includes: position crane 1 location, truck 2 locations; sling & unsling item, raise, position, release load.

000.33834 hours per JOB SETUP TIME

000.38531 hours per items

BT 048 Move major items from first and upper floors of one location to first and upper floors of another location, using a crane and truck.

Includes: position crane & truck 2 locations, sling & unsling raise position release load; hand carry item to new location.

000.50842 hours per JOB SETUP TIME

000.66703 hours per items

BT 049 Move major items from warehouse to office building, first or second floor location.

Includes: move truck to warehouse & office, locate major item & move to truck, lash & unlash load; move major item to new location.

000.25098 hours per JOB SETUP TIME

000.12834 hours per items

BT 050 Move major items from warehouse to upper floor of building using a truck and crane.

Includes: position truck at warehouse & building; locate majo item & move to truck; lash & unlash load; position crane sling unsling; raise position & release; move major item to new locatio

000.42106 hours per JOB SETUP TIME

000.41006 hours per items

BT 033 Measure major items for clearance.

000.01220 hours per items

BT 034 Disassemble or assemble legs, stops, desk steps, and other removable obstructions.

Includes: time to dissassemble & assemble an item as 1 table leg.

000.02200 hours per items

: Reeving
: Tasks include time to remove, install, and replace various types
: of reeving equipment. (1)Winch cable and hook;(2)Auxiliary hoist
: cable; (3)Topping hoist cable; (4)Main hoist cable; (5)Main and
: topping hoist cable; (6)Yard derrick;
:

#### TASK TIME STANDARDS LISTING

BT	067	Winch cable & hook	(remove & reinstall)
BT	071	Auxiliary hoist cable	<pre>(remove &amp; reinstall)</pre>
BT	068	Topping hoist cable	<pre>(remove &amp; reinstall)</pre>
BT	069	Main hoist cable	(remove & reinstall)
BT	070	Main & topping hoist cables	<pre>(remove &amp; reinstall)</pre>
BT	116	Yard derrick	(reeve sections)

EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

\_\_\_\_\_

BT 067 Remove old cable from winch and hook and install new cable.

Includes: unwind old & rewind new cable; loosen set screw & rmv cable end from winch; position thimble eye & hook; make standard 6 strand wire rope end splice; insert seized end in winch drum access & tighten set screw & pound winch cable to drum with heavy hammer.

000.66755 hours per winch cable and hooks

000.00200 hours per feet of cable

BT 071 Remove auxiliary hoist from crane & reinstall.

Includes: unreeve old cable from drum & set on pallet; let ou remaining cable on wench drum: reeve new cable or rewind old

remaining cable on wench drum; reeve new cable or rewind old cable on drum; take up & pull taut first layer of cable.

001.52372 hours per auxiliary hoist cable

000.00200 hours per feet of cable

BT 068 Remove topping hoist cable from bridle assembly on crane and reinstall.

Includes: position crane at site; position A-frame under boom & lower; unreeve cable from drum & set on pallet; let out remai ing on drum; lash boom pennants above bridle & unlash; pour dea end socket; reeve new toppinghoist cable to bridle, take upinspec

003.22897 hours per topping hoist cable

000.00200 hours per feet of cable

BT 069 Remove main hoist cable, hook and fall block on crane and reinstall.

Includes:position crane & support for boom, lower boom;unreev reeve from drum & block sheaves, set on pallet; let out remain ing cable on winch drum; position truck with new set; raise postion load unload release load; pour test new socket;inspect uni

003.94995 hours per main hoist cables

000.00200 hours per feet of cable

BT 070 Remove main and topping hoist from hook, fall block and bridle assemble on crane and reinstall.

Includes: position crane; support boom; unreeve, reeve fall block sheaves, topping hoist, let out remaining drum cable, las & unlash bridle; pour sockets for hock & bridle; using chain falls position &reinstall fall block& bridle& reeve, test, inspec

006.54740 hours per main and topping hoist cables

000.00200 hours per feet of cable

BT 116 Reeve sections on a yard derrick (fore, mid, or aft sections), 12 sheaves per section.

Includes: reeve & unreeve 1600' of yard derrick cables.

003.96360 hours per sections

: SCAFFOLD TASK:include time to assemble,move,level,raise & lower. :

: 1. PORTABLE PIPE SCAFFOLDING 2. PREFABRICATED PIPE SCAFFOLDING 3. SNAP ON ALUM.TYPE SCAFFOLD 4. POWERED SCAFFOLDING

: Task in 1 & 2 are in a formula format. That is you will need to fill in the number of total units that are ground sections & the total number of additional sections that are above and not in contact with the ground.

· •\_\_\_\_\_\_

#### TASK TIME STANDARDS LISTING

BT 185 Prefabricated pipe scaffold- "N" sections high; (assemble or disassemble)

BT 186 Portable scaffold-"N" sections high; (assemble or disassemble)

5ftx6ft SECT.

BT 184 Portable scaffold- snap-on aluminum (assemble or disassemble) (ground level only) 7ftx6ft to 8ft SECT.

BT 175 Powered scaffold- raise and lower.

#### EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

\_\_\_\_\_

BT 185 PREFABRICATED SCAFFOLDING 5'x6'sections ASSEMBLE OR DISASSEMBLE ground level & or additional levels, up to 5 levels.

Includes: position & install end frames sections; install cros bars sections; move scaffold boards into place; position shims, adjust level, tap with hammer to align & all similar motions needed to join bottom & additional sections above ground sections

000.33365 hours per ground sections used (total number of 5'x6' sections on ground)

000.32068 hours per addl.sect.(total no.of 5'x6'sections above ground level sect.)

BT 186 PORTABLE SCAFFOLDING 5'x6' sections ASSEMBLE OR DISASSEMBLE ground level & or additional levels, up to 5 levels.

Includes: bottom section-(roll into place, lock wheels, clam 4 cross bars & brackets into place, move boards into place & attach.), addl.-move additional sections & boards up in place, clamp 4 cross bars & 4 cross brackets into place.

000.19495 hours per ground sections used (total number of 5'x6' sections on ground)

000.31600 hours per addl.sect.(total no.of 5'x6'sections above ground level sect.)

BT 184 Assemble or disassemble "snap on" portable aluminum scaffolding 7' high, 6'to 8' long, and 4.5' wide at ground level (one level high, two man job) parts include: 2 end frames, 4 diagonal braces, and 2 platforms. Ground level assembly only

000.06235 hours per sections

BT 175 Move, level, raise and lower powered scaffolding (portable electric highlift).

Includes: roll power scaffold into place; set 4 jack stands i to place; connect 2 side outrigger rods; crank jackstands to level scaffold; raise power scaffold to exact height; lower powe scaffold to bottom level; raise jackstands.

19

000.65966 hours per occurrences

```
: Shop operations :
: Shop operations :
: Tasks include time for pouring and testing sockets, remove and : reinstall socket to cable, fabricate slings, splice ropes, and : swage wire rope cables. (1,2,3)Socket; (4,5,6,7,10)Sling; : (8,9)Rope, splice; :
```

#### TASK TIME STANDARDS LISTING

```
BT 075
         Socket-
                      up to 5/8";
                                        (pour and test)
        Socket- 3/4" to 1-1/2"; (pour and test)

Socket- up to 1-1/2"; (remove & reinstall to new cable)
BT 073
       Socket-
BT 074
BT 072
       Sling, Wire rope with clips, up to 1-1/2" dia; (fabricate)
BT 076
       Sling, Nylon rope;
                                                              (fabricate)
BT 077
        Sling, simple Wire rope;
                                                              (fabricate)
BT 079
        Sling, Manila rope;
                                                            (fabricate)
BT 117
         Sling,
                Wire rope cable;
                                                            (swage)
BT 078
                  Manila rope;
                                                       short(splice)
BT 080
                  Nylon rope;
                                                       short(splice)
```

## EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

BT 075 Pour socket (up to 5/8"), including test.

Includes: obtain mat'ls; attach socket to cable; unlay wire, straighten, clean, wipe, acid dip each strand; set zinc pot, carry lsdle & pour into socket; position to shear & vice as req; heat socket with torch; test socket- position and clamp or shackle ends, hand pump & wait 12 min process time.

001.22069 hours per sockets

BT 073 Pour socket (3/4" to 1-1/2"), including hydraulic test.

Includes: obtain mat'ls, attach socket to cable, unlay wirestraighten, clean, wipe, acid dip each strand; set zinc pot, ladle, & pour into socket, position to shear & vice as required heat socket with torch. Test socket-obtain cable & position end attaching& rmv shackles; hand pump & process wait 12 min.

001.44157 hours per sockets

BT 074 Remove and reinstall socket to new cable (up to 1-1/2").

Includes: cut wire rope to length with cable shears; remove old socket from cable; pour socket; test socket.

001.74652 hours per sockets

\_\_\_\_\_\_

BT 072 Fabricate wire rope sling with thimble secured with wire rope clips (up to 1-1/2" diameter).

Includes: cutting wire rope to length ;measure 7 mark wire rope 4 places & make 2 bends;measure 7 bend loop; position wire in shears-(thimble or U bolt; cable & socket in vice or remove) position thimble in loops & attach 12 clips;tighten &loosen vic

000.80687 hours per slings

BT 076 Fabricate nylon rope sling.

Includes: make short splice with nylon rope- pound & roll completed splice to smooth splice.

000.36237 hours per slings

BT 077 Fabricate simple wire rope sling and tag.

Includes: fabricate simple sling using standard 6-strand wire rope splices & tag; apply serving to splice.

001.14757 hours per slings

BT 079 Fabricate manila rope sling.

Includes: all actions to loose, wip, trim, form 2 splices to make sling.

000.60562 hours per slings

BT 117 Swage wire rope cable sling.

Includes: cut cable to length; assemble swedge clamp to cable set swage cable & die in press & press.

000.12038 hours per slings

BT 078 Make short splice with manila rope.

Includes: all actions required to loose, splice, trim, and size form splice.

000.30281 hours per splices

BT 080 Make short splice with nylon rope.

Includes: all actions required to make the splice.

000.36237 hours per splices

:
 Weight Capacity Testing
: Tasks include time to obtain test weights, perform 360 degree
: swing test, boom load test, load test with outriggers retracted,
: side load test while travelling forward and backward, forklift
: test, overload test, additional overload test, 12 minute over! load test and fill out test inspection report. All equipment is
: to be tested at 150% of its rated capacity. (1)Truck crane;
: (2)Telescopic truck/Crawler cranes; (3)Forklift; (4)Hoisting
: equipment;
:

#### TASK TIME STANDARDS LISTING

BT 017 Truck Crane, up to 45 ton capacity.

BT 018 Telescopic Truck Crane or Crawler Crane, up to 45 ton capacity.

BT 019 Forklift trucks.

BT 020 Hoisting Equipment, up to 15 ton capacity.

## EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

BT 017 Weight capacity test crane at 150% of rated capacity (up to 45 ton crane).

Includes: position hydraulic crane adjacent to unit; attach & remove sling; raise, position & release weights & return them t truck, attach & rmv addl padeyes & sling; raise, position & relea e wts; pull chain hoist, make hook&link test measure&inspect cran

004.13370 hours per cranes

000.29150 hours per weights

BT 018 Weight capacity test telescopic truck crane or crawler crane, up to 45 ton capacity at 150% of rated capacity.

Includes: obtain test wts. in yard; preform boom load test on unit; fill out test report.

002.16305 hours per cranes

000.29150 hours per weights

BT 019 Weight capacity test forklift trucks. Test at 150% of rated capacity.

Includes: weight capacity test and fill out inspection report

001.25357 hours per trucks

\_\_\_\_\_

BT 020 Weight capacity test hoisting equipment, up to 15 ton capacity (bridge, trolley, chain, jib, A-frame or monorail) at 150% of rated capacity.

Includes: position unit, attach & rmv sling obtain return wt. attach sling & pad eyes; lift load-wait; make measurements & inspect; fill out inspection report.

23

002.60563 hours per units

: Time for loading (or unloading) bulldozer (or similar weighting up to 75 tons) onto folding gooseneck/removable gooseneck trailer assumes that the 12 horse power hydraulic self-lifting system is being used under ideal weather conditions (60 to 80 degrees F).

#### TASK TIME STANDARDS LISTING

BT 200 GOOSENECK TRAILER - hydraulic, self-lifting LOAD & UNLOAD time for tie downs not included

BT 201 GOOSENECK TRAILER - hydraulic, self-lifting LOAD & UNLOAD time for tie downs included

EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

\_\_\_\_\_

BT 200 Load and unload bulldozer (or similar) onto folding gooseneck (removable gooseneck) trailer with hydraulic self-lifting/lower ing system

--tie down time not included

000.25506 hours per "load and unload" tasks

BT 201 Load and unload bulldozer (or other heavy equipment) on/off folding gooseneck (removable gooseneck) trailer using hydraulic selflifting-lowering system

--tie down time included

000.43809 hours per "load and unload" of heavy equipment

For positioning of concrete street barriers, there's a backhoe operator and a person to secure chains to barriers. Transportation time of heavy equipment or barriers prior to and subsequent to placing or removing concrete street barrier is not included:

### TASK TIME STANDARDS LISTING

BT 202 CONCRETE STREET BARRIERS - place to exact location per BARRIER

EPS TASK TIME STANDARDS - DESCRIPTIONS AND UNIT HOURS

\_\_\_\_

BT 202 Place (or remove) concrete street barrier with heavy equipment
--position to exact location within heavy equipment's reach
--two men job
includes: position chains on barrier; secure chains; lift, turn
and place barrier; take off chains; reach for next barrier.

000.03406 hours per barriers

## TASK TIME STANDARDS DEVELOPMENT BACKUP

- BT 001 1 REMOVE WIRE ROPE TIE DOWNS
  - 2 REMOVE CRIBBING AND CHOCKS
  - 3 SLING CLAM BUCKET, DRAGLINE BUCKET, BOOM SECTION AND 3 BOXES OF SPARE PARTS
  - 4 RAISE, POSITIONS AND RELEASE LOADS
  - 5 POSITION CRANE
  - 6 MOVE CRANE OFF RAILROAD CAR APPROXIMATELY 50 YARDS
- BT 002 1 POSITION CRANE & LOWBED TRUCK AT LOAD & UNLOAD POINTS
  - 2 POSITION LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 3 SLING AND UNSLING TRAILER AT LOAD AND UNLOAD POINT
  - 4 PLACE DUNNAGE ON TRUCK TO SET TRAILER AND REMOVE
  - 5 LOAD AND UNLOAD 6 CONCRETE PIERS
  - 6 POSITION PIERS
  - 7 RAISE, POSITION AND RELEASE TRAILER
- BT 004 1 POSITION CRANE AND LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 2 POSITION LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 3 ATTACH AND REMOVE SLINGS AT LOAD AND UNLOAD POINTS
  - 4 RAISE, POSITION AND RELEASE PLATES AT LOAD AND UNL OAD POINTS
  - 5 SET DUNNAGE ON LOWBED TRUCK
  - 6 MOVE TWO PLATES TO SELECT DESIRED PLATE
- BT 005 1 POSITION CRANE AT LOAD AND UNLOAD POINTS
  - 2 POSITION LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 3 SLING AND UNSLING LOAD AT LOAD AND UNLOAD POINTS
  - 4 RAISE, POSITION AND RELEASE LOAD AT LOAD AND UNLOAD POINTS
  - 5 LASH AND UNLASH LOAD CHAIN BINDERS
  - 6 PLACE DUNNAGE TO SET LOAD AND REMOVE
- BT 007 1 POSITION CRANE AND LOWBED AT LOAD AND UNLOAD POINT
  - 2 POSITION LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 3 PLACE DUNNAGE AND REMOVE ONE INSTALL AND ONE REMOV E PER 5 BUNDLES
  - 4 SLING AND UNSLING BUNDLES AT LOAD AND UNLOAD POINT
  - 5 RAISE, POSITION AND RELEASE LOADS AT LOAD AND UNLO AD POINTS
- BT 017 1 PERFORM 360 DEGREE SWING TEST ON TRUCK CRANE
  - 2 PERFORM BOOM LOAD TEST ON TRUCK OR CRAWLER CRANE
  - 3 PERFORM LOAD TEST ON TRUCK CRANE, OUTRIGGER RETRAC
  - 4 PERFORM SIDE LOAD TEST, TRUCK CRANE, TRAVELING 50 FEET FORWARD AND 50 FEET BACKWARD
  - 5 FILL OUT CRANE TEST INSPECTION REPORT

- BT 018 1 OBTAIN TEST WEIGHTS IN TEST YARD
  - 2 PERFORM BOOM LOAD TEST ON TRUCK OR CRAWLER CRANE
  - 3 FILL OUT CRANE TEST INSPECTION REPORT
- BT 019 1 WEIGHT CAPACITY TEST FORKLIFT
  - 2 FILL OUT INSPECTION REPORT FORM
- BT 020 1 POSITION SMALL HYDRAULIC 5 TON CRANE (SUCH AS TORP EDO OF DOCK SIDE) ADJACENT TO HOIST (MONORAIL, BRI
  - 2 ATTACH AND REMOVE SLING TO WEIGHT BRACKET AND CRAN E HOOK; REPEAT FOR HOIST HOOK; RETURN WEIGHTS TO T
  - 3 RAISE, POSITION AND RELEASE COUNTERWEIGHTS UNDER HO IST (10,000#); RETURN WEIGHTS TO TRUCK
  - 4 ATTACH AND REMOVE TEMPORARY PADEYES (2) TO ADDITIONAL OVERLOAD WEIGHT
  - 5 ATTACH AND REMOVE SLING TO TWO (2) PADEYES AND TO CRANE AND TEST HOIST HOOKS FOR ADDITIONAL OVERLOAD
  - 6 RAISE, POSITION TO OTHER WEIGHTS AND RELEASE ADDIT IONSL OVERLOAD WEIGHT; RETURN TO TRUCK
  - 7 LIFT LOAD, PERFORM 12 MINUTE OVERLOAD TEST
  - 8 INSPECT AND MEASURE 5 CHAIN LINKS, INSPECT CONDITI ON OF CRANE, SHAFTING, GEARS, TRACKS, CABLE AND BL
  - 9 FILL OUT CRANE TEST INSPECTION REPORT
- BT 023 1 RAISE HEAVY PART WITH HYDRAULIC JACKS AND BLOCKING , PLACE ON DOLLIES OR ROLLER
  - 2 PULL HEAVY PART ON AVG. OF 50 FEET USING BLOCK AND TACKLE
- BT 024 1 RELOCATE HEAVY MACHINERY OR EQUIPMENT
  - 2 POSITION CRANE AND LOWBED AT LOAD AND UNLOAD POINT S
  - 3 POSITION LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 4 SLING AND UNSLING LOAD AT LOAD AND UNLOAD POINTS
  - 5 RAISE, POSITION AND RELEASE LOAD AT LOAD AND UNLOAD POINTS
  - 6 LASH AND UNLASH TO TRUCK
- BT 028 1 MOVE MINOR ITEMS TO NEW LOCATION
- BT 029 1 MOVE MAJOR ITEMS TO NEW LOCATION (2 MEN)
- BT 030 1 POSITION SMALL CRANE
  - 2 ATTACH AND REMOVE SLING FROM MAJOR ITEM
  - 3 RAISE, POSITION AND RELEASE LOAD
  - 4 MOVE MAJOR ITEM TO NEW LOCATION
- BT 031 1 MOVE MINOR ITEMS TO TRUCK AND FROM TRUCK TO NEW LO CATION NOTE: TRUCK INCLUDED IN MAJOR ITEMS

- BT 032 1 POSITION TRUCK AT 2 LOCATIONS
  - 2 MOVE MAJOR ITEM TO NEW LOCATION
- BT 033 1 MEASURE, MARK AND CHECK MEASURE OF MAJOR ITEMS
- BT 034 1 INSTALL OR REMOVE SMALL NUT OR SCREW HOLDING DESK LEG OR STOP
  - 2 DISASEMBLE OR ASSEMBLE DESK LEGS, STOPS TO FIT THR OUGH DOOR
- BT 047 1 POSITION CRANE AT ONE LOCATION
  - 2 POSITION TRUCK AT TWO LOCATIONS
  - 3 ATTACH AND REMOVE SLING FROM MAJOR ITEMS
  - 4 RAISE, POSITION AND RELEASE LOAD
  - 5 MOVE MAJOR ITEM TO NEW LOCATION
- BT 048 1 POSITION CRANE AT 2 LOCATIONS
  - 2 POSITION TRUCK AT 2 LOCATIONS
  - 3 ATTACH AND REMOVE SLING FROM MAJOR ITEM
  - 4 RAISE, POSITION AND RELEASE LOAD
  - 5 MOVE MAJOR ITEM TO NEW LOCATION
- BT 049 1 MOVE TRUCK TO WAREHOUSE DOCK AND TO BUILDING LOCAT ION (2 MEN)
  - 2 LOCATE MAJOR ITEM IN WAREHOUSE, MOVE TO TRUCK
  - 3 LASH AND UNLASH LOAD
  - 4 MOVE MAJOR ITEM TO NEW LOCATION
- BT 050 1 POSITION TRUCK AT WAREHOUSE AND BUILDING
  - 2 LOCATE MAJOR ITEM IN WAREHOUSE, MOVE TO TRUCK
  - 3 LASH AND UNLASH LOAD
  - 4 POSITION CRANE
  - 5 ATTACH AND REMOVE SLING FROM MAJOR ITEM
  - 6 RAISE, POSITION AND RELEASE LOAD
  - 7 MOVE MAJOR ITEM TO NEW LOCATION
- BT 055 1 POSITION 5 TON CRANE AT LOAD AND UNLOAD POINTS
  - 2 POSITION LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 3 SLING AND UNSLING LOAD AT LOAD AND UNLOAD POINTS
  - 4 RAISE, POSITION AND RELEASE LOADS
- BT 056 1 POSITION CRANE AT LOAD AND UNLOAD POINTS
  - 2 POSITION LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 3 SLING AND UNSLING TREE
  - 4 RAISE, POSITION AND RELEASE LOAD (TWO TIMES) (ONCE TO PULL AND SHAKE EARTH FROM ROOTS, ONCE ON LOWBE
  - 5 LASH AND UNLASH TREE TO LOWBED TRUCK
  - 6 PULL TREE TO AND FROM LOWBED TRUCK AT DUMP

- BT 059 1 POSITION CRANE AT POLES
  - 2 ATTACH AND REMOVE SLING TO BASKET
  - 3 ATTACH AND REMOVE TAGLINE TO BASKET
  - 4 CONNECT AND DISCONNECT SAFETY CABLE
  - 5 RAISE, POSITION AND LOWER PERSONNEL BASKET TO MEAS URE AND INSTALL BOLTS
  - 6 ATTACH AND REMOVE TAGLINES (2) TO PLATFORM
  - 7 SLING AND UNSLING PLATFORM AND CRADLE
  - 8 RAISE, POSITION AND RELEASE PLATFORM AND CRADLE
  - 9 SLING AND UNSLING LOAD
  - 10 RAISE, POSITION AND RELEASE LOAD ON CRADLE
- BT 061 1 PLACE TANK ON DOLLIES WITH JACKS
  - 2 ROLL OUT/IN BUILDING
  - 3 SLING TO LIFT ON AND OFF TRUCK
  - 4 POSITION CRANE AND LOWBED AT LOAD AND UNLOAD POINT
  - 5 POSITION LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 6 RAISE, POSITION AND RELEASE LOAD AT LOAD AND UNLOAD POINTS
  - 7 LASH AND UNLASH TO TRUCK TO TRANSPORT
- BT 064 1 DISASSEMBLE AND ASSEMBLE TIE RODS
  - 2 POSITION CRANE AND LOWBED AT LOAD AND UNLOAD POINT S
  - 3 POSITION LOWBED TRUCK AT LOAD AND UNLOAD POINTS
  - 4 SLING AND UNSLING FRONT AND REAR SECTIONS AND UPRI GHT SUPPORTS AT LOAD AND UNLOAD POINTS
  - 5 RAISE, POSITION AND RELEASE LOADS AT LOAD AND UNLO AD POINTS
  - 6 LASH AND UNLASH LOAD
- BT 067 1 UNWIND OLD CABLE AND REWIND NEW CABLE
  - 2 LOOSEN SET SCREW
  - 3 REMOVE CABLE END FROM WINCH
  - 4 POSITION THIMBLE EYE AND HOOK
  - 5 FABRICATE STANDARD 6-STRAND WIRE ROPE END SPLICE
  - 6 INSERT SEIZED END IN WINCH DRUM RECESS
  - 7 TIGHTEN SET SCREW
  - 8 POUND (ALIGN) WINCH CABLE TO DRUM WITH HEAVY HAMME R
- BT 068 1 POSITION CRANE AT RIGGING
  - 2 POSITION BOOM SUPPORT A-FRAME UNDER BOOM
  - 3 LOWER BOOM TO REST ON A-FRAME
  - 4 UNREEVE OLD CABLE FROM DRUM AND SET ON PALLET
  - 5 LET OUT REMAINING CABLE ON WINCH DRUM
  - 6 LASH BOOM PENNANTS ABOVE BRIDLE ASSEMBLY AND UNLAS H
  - 7 POUR DEAD END SOCKET
  - 8 REEVE NEW TOPPING HOIST CABLE TO BRIDLE ASSEMBLY
  - 9 TAKE UP AND PULL TAUT FIRST LAYER OF CABLE ON WINC H DRUM
  - 10 TEST CRANE, (RAISE BOOM TO LIMIT AND RETURN)
  - 11 REMOVE OLD SOCKET FROM CABLE

- BT 069 1 POSITION CRANE
  - 2 POSITION BOOM SUPPORT A-FRAME UNDER BOOM
  - 3 LOWER BOOM TO REST ON A-FRAME AND LOWER HOOK TO GR
  - 4 UNREEVE OLD CABLE FROM DRUM AND FALL BLOCK SHEAVES AND SET ON PALLET
  - 5 LET OUT REMAINING CABLE ON WINCH DRUM
  - 6 POSITION BOOM TRUCK FORWARD AND BACK TO FALL BLOCK AND HOOK RETURN WITH NEW SET
  - 7 RAISE, POSITION AND LOWER CHAIN FALLS TO BLOCK, LO AD AND UNLOAD, RETURN WITH NEW SET
  - 8 ATTACH AND REMOVE CHAIN FALLS TO CRANE FALL BLOCK AND HOOK
  - 9 POUR NEW DEAD END SOCKET
  - 10 REEVE NEW MAIN HOIST CABLE HOOK AND FALL BLOCK
  - 11 TAKE UP AND PULL TAUT FIRST LAY OF CABLE ON WINCH DRUM
  - 12 TEST CRANE (RAISE BOOM AND HOOK TO VERTICAL LIMIT AND LOWER)
  - 13 INSPECT CABLE HOOK AND FALL BLOCK, CHECK FOR TWIST ING
  - 14 REMOVE OLD SOCKET FROM CABLE
  - 15 TEST NEW SOCKET

### BT 070 1 POSITION CRANE AT RIGGING LOFT

- 2 POSITION BOOM SUPPORT A-FRAME UNDER BOOM
- 3 LOWER BOOM TO REST ON A-FRAME AND LOWER HOOK TO GR
- 4 UNREEVE OLD CABLE FROM DRUM AND FALL BLOCK SHEAVES AND SET ON PALLET
- 5 UNREEVE OLD TOPPING HOIST CABLE FROM BRIDLE ASSEMB LY AND SET ON PALLET
- 6 LET OUT REMAINING CABLE ON BOTH WINCH DRUMS
- 7 LASH BOOM PENNANTS ABOVE BRIDLE ASSEMBLY AND UNLAS
- 8 POUR TWO NEW DEAD END SOCKETS FOR HOOK AND BRIDLE ASSEMBLY DEAD ENDS
- 9 POSITION BOOM TRUCK FORWARD AND BACK TO FALL BLOCK AND HOOK, RETURN WITH NEW SET
- 10 RAISE, POSITION AND LOWER CHAIN FALLS TO BLOCK, LO AD AND UNLOAD, RETURN WITH NEW SET
- 11 ATTACH AND REMOVE CHAIN FALLS TO CRANE FALL BLOCK AND HOOK
- 12 REEVE NEW TOPPING LIFT CABLE TO BRIDLE ASSEMBLY
- 13 REEVE NEW MAIN HOIST CABLE, HOOK AND FALL BLOCK
- 14 TAKE UP AND PULL TAUT FIRST LAYER OF CABLE ON WINC H DRUM
- 15 TEST CRANE (RAISE BOOM AND HOOK TO VERTICAL LIMIT AND LOWER)
- 16 INSPECT CABLE HOOK AND FALL BLOCK FOR TWISTING
- 17 REMOVE OLD SOCKET FROM CABLE
- 18 TEST NEW SOCKETS

- BT 071 1 UNREEVE OLD CABLE FROM DRUM AND SET ON PALLET
  - 2 LET OUT REMAINING CABLE ON WINCH DRUM
  - 3 REEVE NEW CABLE OR REWIND OLD CABLE ON DRUM
  - 4 TAKE UP AND PULL TAUT FIRST LAYER OF CABLE
- BT 072 1 FABRICATE WIRE ROPE SLING WITH THIMBLE. INCLUDES S EIZINGS, CUTTING WIRE ROPE TO LENGTH AND INSTALLIN
- BT 073 1 POUR SOCKET
  - 2 TEST SOCKET
- BT 074 1 CUT WIRE ROPE TO LENGTH WITH CABLE SHEARS
  - 2 REMOVE OLD SOCKET FROM CABLE
  - 3 POUR SOCKET (UP TO 1 1/2")
  - 4 TEST SOCKET
- BT 075 1 POUR SOCKET
  - 2 TEST SOCKET
- BT 076 1 MAKE SHORT SPLICE WITH NYLON ROPE
- BT 077 1 FABRICATE SIMPLE SLING USING STANDARD 6-STRAND WIR E ROPE SPLICES AND TAG
  - 2 APPLY SERVING TO SPLICE
- BT 078 1 MAKE SHORT SPLICE WITH MANILA ROPE
- BT 079 1 MAKE SHORT SPLICE WITH MANILA ROPE
- BT 080 1 MAKE SHORT SPLICE WITH NYLON ROPE
- BT 097 1 ATTACH WITH SLINGS AND HOOKS TO 4 PADEYES ON CAMEL
  - 2 RAISE CAMEL, LOWER, POSITION AND SET ON FORKLIFTS AND RELEASE
  - 3 PROCESS TIME, POSITION FORKLIFTS TO RECEIVE CAMEL
- BT 104 1 POSITION CRANE
  - 2 ATTACH AND RELEASE SLING
  - 3 RAISE, POSITION AND RELEASE LOAD
  - 4 ADDITIONAL CRANE TRAVEL
- BT 111 1 POSITION CRANE
  - 2 ATTACH AND REMOVE SLING
  - 3 RAISE, POSITION AND RELEASE LOAD
  - 4 ADDITIONAL CRANE TRAVEL
- BT 113 1 POSITION CRANE AT CONCRETE BLOCK
  - 2 POSITION LOWBED TRUCK AT CONCRETE BLOCK
  - 3 ATTACH SLING TO CRANE HOOK
  - 4 ATTACH AND DETACH SLING TO CONCRETE BLOCK
  - 5 RAISE AND POSITION CONCRETE BLOCK ON LOWBED TRUCK
  - 6 POSITION CRANE AT TARGET AREA
  - 7 POSITION LOWBED TRUCK AT TARGET AREA
  - 8 ATTACH AND DETACH SLING TO CONCRETE BLOCK
  - 9 SET CONCRETE BLOCK IN EXACT LOCATION

- BT 114 1 POSITION CRANE AT STEEL ARTILLERY TARGET
  - 2 ATTACH SLING TO TARGET
  - 3 RAISE TARGET
  - 4 POSITION CRANE AND TARGET AT CONCRETE BLOCK
  - 5 SET TARGET IN EXACT LOCATION
- BT 116 1 REEVE YARD DERRICK SECTION CABLES
  - 2 UNREEVE YARD DERRICK SECTION CABLES
- BT 117 1 CUT CABLE TO LENGTH
  - 2 ASSEMBLE SWAGE CLAMP TO CABLE
  - 3 SET SWAGE DIE IN PRESS
  - 4 SET SWAGE CABLE IN PRESS
- BT 135 1 CLIMB TOWER TO DISK LOCATION LEVEL
  - 2 RAISE AND LOWER TOOL BAG AND MATERIALS
  - 3 CONNECT CHAIN FALL TO TOWER BAR AND DISCONNECT
  - 4 REEVE WINCH CABLE THROUGH CHAIN FALL
  - 5 PULL CATWALK, LUGALL JACK, JIB POLE TO DISK LOCATION WITH WINCH (120 FT);720 FT TOTAL
  - 6 SECURE CATWALK TO TOWER
  - 7 SECURE JIB POLE AND JACK TO TOWER
  - 8 HOIST TRANSMITTER DISK TO POSITION; 720 FEET TOTAL
  - 9 SECURE DISK TO TOWER
- BT 136 1 POSITION CRANE NEAR TOWER
  - 2 CLIMB TOWER SECTION
  - 3 RAISE AND LOWER TOOL BAG
  - 4 RAISE BOOM TO SECTION
  - 5 ATTACH SLINGS TO TOWER SECTION
  - 6 DISASSEMBLE SECTION BOLTS
  - 7 LOWER SECTION TO GROUND
- BT 137 1 POSITION CRANE NEAR TOWER
  - 2 POSITION WINCH TRUCK NEAR TOWER SECTION
  - 3 ATTACH WINCH CABLE TO TOWER SECTION
  - 4 ATTACH SLING TO TOWER SECTION
  - 5 CLIMB TOWER SECTION
  - 6 RAISE AND LOWER TOOL BAG
  - 7 RAISE TOWER SECTION (30 FT AVERAGE SECTION)
  - 8 ASSEMBLE SECTION BOLTS
- BT 138 1 POSITION CRANE AT LOAD AND UNLOAD POINTS
  - 2 POSITION LOWBED TRUCK AT LOAD AND UNOAD POINTS
  - 3 WALK THROUGH BUILDING UP TO ROOF AND RETURN
  - 4 SLING AND UNSLING HVAC UNIT AT LOAD AND UNLOAD POI
  - 5 RAISE, POSITION, AND RELEASE UNIT

- BT 139 1 POSITION CRANE
  - 2 CLIMB UP AND DOWN POLE
  - 3 SLING AND UNSLING TRANSFORMERS
  - 4 RAISE, POSITION AND RELEASE LOAD
- BT 140 1 POSITION CRANE (DOES NOT INCLUDE MOVING CRANE BY T UGBOAT)
  - 2 ATTACH AND REMOVE SLINGS TO A LOAD OF STEEL AND A LOAD OF DUNNAGE
  - 3 RAISE, POSITION AND RELEASE LOAD
  - 4 POSITION DUNNAGE UNDER LOAD
- BT 141 1 POSITION CRANE
  - 2 WALK THROUGH BUILDING UP TO ROOF AND RETURN (200 P ACES, 2 MEN)
  - 3 RIG CHAIN FALL AND HOIST TO OVERHEAD BEAM AND REMO VE
  - 4 INSTALL OR REMOVE RETAINING SCREWS
  - 5 SLING AND HOIST FILTER
  - 6 MOVE FILTER TO CRANE SLING (20 PACES)
  - 7 SLING FILTER TO CRANE (TRANSFER FROM HOIST TO CRAN E)
  - 8 RAISE AND HOIST FILTER, LOWER TO GROUND (OPERATOR, SIGNALMAN, AND RIGGER)
- BT 143 1 POSITION CRANE
  - 2 LASH OR UNLASH LOAD, CHAIN AND BINDER
  - 3 ATTACH AND REMOVE SLINGS
  - 4 RAISE, POSITION AND RELEASE LOAD
- BT 146 1 POSITION CRANE (DOES NOT INCLUDE MANEUVERING OF CR ANE BY TUGBOAT)
  - 2 ATTACH AND REMOVE SLING FROM TANK
  - 3 RAISE, POSITION AND RELEASE LOAD
- BT 149 1 POSITION CRANE (DOES NOT INCLUDE MANEUVERING OF CR ANE BY TUGBOAT)
  - 2 ATTACH AND REMOVE SLING TO CRANE CAB TWICE; AND TO EACH DIESEL ENGINE ONCE
  - 3 RAISE, POSITION AND RELEASE LOADS
- BT 159 1 POSITION CRANE NEAR YARD DERRICK
  - 2 RAISE AND LOWER BOOM
  - 3 HOOK AND UNHOOK STEEL FENDER
  - 4 HOLD FENDER FOR CUTTING (PROCESS TIME)
  - 5 LIFT AND ASIDE FENDER TO YARD
- BT 160 1 POSITION CRANE NEAR YARD DERRICK
  - 2 RAISE AND LOWER BOOM
  - 3 HOOK AND UNHOOK RUBBER FENDER
  - 4 HOLD FENDER FOR BOLT REMOVAL
  - 5 LIFT AND ASIDE FENDER TO YARD
  - 6 HOLD NEW FENDER IN PLACE FOR DRILLING BOLT HOLES
  - 7 HOLD FENDER IN PLACE FOR BOLT INSTALLATION

- BT 161 1 POSITION LOAD
  - 2 POSITION FLATBED TRAILER
  - 3 ATTACH OR REMOVE CRANE HOOK
  - 4 RAISE, POSITION AND RELEASE LOAD
  - 5 LASH OR UNLASH LOAD TO TRAILER (AVERAGE LOAD 3 ITE MS)
- BT 162 1 LOAD AND UNLOAD BOW OR STERN FENDER AT STORAGE YAR
- BT 163 1 POSITION CRANE
  - 2 ATTACH OR REMOVE CRANE HOOK
  - 3 RAISE, POSITION AND RELEASE LOAD
  - 4 TRANSPORT FENDER WITH FORK LIFT
  - 5 POSITION FORKLIFT
- BT 164 1 POSITION CRANE
  - 2 INSTALL OR REMOVE SHACKLES
  - 3 INSTALL OR REMOVE SHACKLE BOLTS
  - 4 ATTACH OR REMOVE CRANE HOOK
  - 5 RAISE, POSITION AND RELEASE LOAD
  - 6 POSITION FLATBED TRAILER
  - 7 LASH OR UNLASH LOAD TO TRAILER (AVERAGE LOAD 3 ITE MS)
- BT 166 1 POSITION CRANE
  - 2 POSITION FORK TRUCK
  - 3 RAISE, POSITION AND RELEASE LOADS
  - 4 ATTACH AND REMOVE SLING
- BT 167 1 POSITION CRANE
  - 2 INSTALL OR REMOVE SHACKLES
  - 3 INSTALL OR REMOVE SHACKLE BOLTS
  - 4 ATTACH OR REMOVE CRANE HOOK
  - 5 RAISE, POSITION AND RELEASE LOADS
  - 6 LASH OR UNLASH LOAD TO TRAILER (AVERAGE LOAD 3 ITE MS)
  - 7 POSITION FLATBED TRAILER
- BT 168 1 POSITION CRANE
  - 2 ATTACH AND REMOVE SLING
  - 3 RAISE, POSITION AND RELEASE LOAD
- BT 170 1 POSITION CRANE
  - 2 ATTACH AND REMOVE SLING
  - 3 RAISE, POSITION AND RELEASE LOAD
  - 4 ADDITIONAL CRANE TRAVEL
  - 5 ADDITIONAL CRANE TRAVEL (FIRST TRAVEL ALREADY ALLO WED)

- BT 173 1 ROLL SCAFFOLDING INTO PLACE
  - 2 LOCK SCAFFOLD WHEELS
  - 3 CLAMP 4 CROSS BARS AND 4 CROSS BRACES INTO PLACE
  - 4 MOVE SCAFFOLD BOARDS INTO PLACE
- BT 174 1 ASSEMBLE OR DISASSEMBLE GROUND LEVEL SECTIONS OF P ORTABLE SCAFFOLDING
  - 2 MOVE UPPER LEVEL SCAFFOLD SECTION TO FIRST LEVEL S ECTION
  - 3 INSTALL SECTION POSTS NEXT LEVEL TO SEAT IN LOWER LEVEL SECTION
  - 4 RAISE SCAFFOLD BOARDS TO NEXT LEVEL
  - 5 CLAMP 4 CROSS BARS AND 4 CROSS BRACES INTO PLACE F OR EACH UPPER LEVEL SECTION
  - 6 MOVE SCAFFOLD BOARDS TO SCAFFOLD AND SET IN PLACE FOR UPPER LEVEL SECTIONS
- BT 175 1 ROLL POWERED SCAFFOLD INTO PLACE
  - 2 SET 4 JACKSTANDS INTO PLACE
  - 3 CONNECT 2 SIDE OUTRIGGER RODS
  - 4 CRANK JACKSTANDS TO LEVEL SCAFFOLD
  - 5 RAISE POWERED SCAFFOLD TO EXACT HEIGHT
  - 6 LOWER POWER SCAFFOLD TO BOTTOM LEVEL
  - 7 RAISE JACKSTANDS
- BT 176 1 POSITION AND INSTALL END FRAMES FOR GROUND LEVEL S ECTIONS (FIRST GROUND LEVEL SECTION REQUIRES ONE A
  - 2 POSITION AND INSTALL END FRAMES FOR GROUND LEVEL S ECTIONS
  - 3 INSTALL CROSS BARS FOR GROUND LEVEL SECTIONS
  - 4 INSTALL CROSS BARS FOR GROUND LEVEL SECTIONS (FIRS T GROUND LEVEL SECTION REQUIRES 2 ADDITIONAL CROSS
  - 5 INSTALL CROSS BRACES FOR GROUND LEVEL SECTIONS
  - 6 MOVE SCAFFOLD BOARDS INTO PLACE FOR GROUND LEVEL S ECTIONS
  - 7 POSITION SHIM
  - 8 LEVEL, TAP WITH HAMMER TO ALIGN
- BT 177 1 ASSEMBLE GROUND LEVEL SECTIONS OF SCAFFOLDING
  - 2 POSITION AND INSTALL END FRAMES FOR UPPER LEVEL SE CTIONS
  - 3 POSITION AND INSTALL END FRAMES FOR UPPER LEVEL SE CTIONS (FIRST UPPER LEVEL SECTION REQUIRES TWO ADD
  - 4 INSTALL CROSS BARS FOR UPPER LEVEL SECTIONS
  - 5 INSTALL CROSS BARS FOR UPPER LEVEL SECTIONS (FIRST UPPER LEVEL SECTION REQUIRES TWO ADDITIONAL CROSS
  - 6 INSTALL CROSS BRACES FOR UPPER LEVEL SECTIONS
  - 7 MOVE SCAFFOLD BOARDS INTO PLACE FOR UPPER LEVEL SE CTIONS (EXTRA MATERIAL HANDLING FOR INCREASED HEIG

- BT 178 1 ASSEMBLE GROUND LEVEL SECTIONS OF SCAFFOLDING
  - 2 POSITION AND INSTALL END FRAMES FOR UPPER LEVEL SE CTIONS
  - 3 POSITION AND INSTALL END FRAMES FOR UPPER LEVEL SE CTIONS (FIRST UPPER LEVEL SECTION AT EACH LEVEL RE
  - 4 INSTALL CROSS BARS FOR UPPER LEVEL SECTIONS
  - 5 INSTALL CROSS BARS FOR UPPER LEVEL SECTIONS (FIRST UPPER LEVEL SECTION AT EACH LEVEL REQUIRES TWO AD
  - 6 INSTALL CROSS BRACES FOR UPPER LEVEL SECTIONS
  - 7 MOVE SCAFFOLD BOARDS INTO PLACE FOR UPPER LEVELS
- BT 179 1 ASSEMBLE GROUND LEVEL SECTIONS OF SCAFFOLDING
  - 2 POSITION AND INSTALL END FRAMES FOR UPPER LEVEL SE
  - 3 POSITION AND INSTALL END FRAMES FOR UPPER LEVEL SE CTIONS (FIRST UPPER LEVEL SECTION AT EACH REQUIRES
  - 4 INSTALL CROSS BARS FOR UPPER LEVEL SECTIONS
  - 5 INSTALL CROSS BARS FOR UPPER LEVEL SECTIONS (FIRST UPPER LEVEL SECTION AT EACH LEVEL REQUIRES TWO AD
  - 6 INSTALL CROSS BRACES FOR UPPER LEVEL SECTIONS
  - 7 MOVE SCAFFOLD BOARDS INTO PLACE FOR UPPER LEVELS
- BT 180 1 ASSEMBLE GROUND LEVEL SECTIONS OF SCAFFOLDING
  - 2 POSITION AND INSTALL END FRAMES FOR UPPER LEVEL SE CTIONS
  - 3 POSITION AND INSTALL END FRAMES FOR UPPER LEVEL SE CTIONS (FIRST UPPER LEVEL SECTION AT EACH LEVEL RE
  - 4 INSTALL CROSS BARS FOR UPPER LEVEL SECTIONS
  - 5 INSTALL CROSS BARS FOR UPPER LEVEL SECTIONS (FIRST UPPER LEVEL SECTION AT EACH LEVEL REQUIRES TWO AD
  - 6 INSTALLCROSS BRACES FOR UPPER LEVEL SECTIONS
  - 7 MOVE SCAFFOLD BOARDS INTO PLACE FOR UPPER LEVELS
- BT 181 1 ASSEMBLE OR DISASSEMBLE GROUND LEVEL SECTIONS OF P ORTABLE SCAFFOLDING
  - 2 MOVE UPPER LEVEL SCAFFOLD SECTION TO FIRST LEVEL S ECTION
  - 3 INSTALL SECTION POSTS NEXT LEVEL TO SEAT IN LOWER LEVEL SECTION FOR EACH UPPER LEVEL SECTION
  - 4 RAISE SCAFFOLD BOARDS TO NEXT LEVEL
  - 5 CLAMP 4 CROSS BARS AND 4 CROSS BRACES INTO PLACE F OR EACH UPPER LEVEL SECTION
  - 6 MOVE SCAFFOLD BOARDS TO SCAFFOLD AND SET IN PLACE FOR UPPER LEVEL SECTIONS
- BT 182 1 ASSEMBLE OR DISASSEMBLE GROUND LEVEL SECTIONS OF P ORTABLE SCAFFOLDING
  - 2 MOVE UPPER LEVEL SCAFFOLD SECTION TO FIRST LEVEL S ECTION
  - 3 INSTALL SECTION POSTS NEXT LEVEL TO SEAT IN LOWER LEVEL SECTION FOR EACH UPPER LEVEL SECTION
  - 4 RAISE SCAFFOLD BOARDS TO NEXT LEVEL
  - 5 CLAMP 4 CROSS BARS AND 4 CROSS BRACES INTO PLACE F OR EACH UPPER LEVEL SECTION
  - 6 MOVE SCAFFOLD BOARDS TO SCAFFOLD AND SET IN PLACE FOR UPPER LEVEL SECTIONS

- BT 183 1 ASSEMBLE OR DISASSEMBLE GROUND LEVEL SECTIONS OF PORTABLE SCAFFOLDING
  - 2 MOVE UPPER LEVEL SCAFFOLD SECTION TO FIRST LEVEL S ECTION
  - 3 INSTALL SECTION POSTS NEXT LEVEL TO SEAT IN LOWER LEVEL SECTION FOR EACH UPPER LEVEL SECTION
  - 4 RAISE SCAFFOLD BOARDS TO NEXT LEVEL
  - 5 CLAMP 4 CROSS BARS AND 4 CROSS BRACES INTO PLACE F OR EACH UPPER LEVEL SECTION
  - 6 MOVE SCAFFOLD BOARDS TO SCAFFOLD AND SET IN PLACE FOR UPPER LEVEL SECTIONS
- BT 184 1 GATHER SCAFFOLDING PARTS AND REPOSITION INSIDE WOR K AREA \*PARTS INCLUDE END FRAMES, DIAGONAL BRACES,
  - 2 WALKING REQUIRED TO GATHER/REPOSITION PARTS \*APPRO X. NUMBER OF ROUND TRIPS TIMES NUMBER FEET \*(5 R.
  - 3 WALKING REQUIRED TO GET/INSTALL EACH SCAFFOLDING PART \*TO GET/POSITION END FRAMES (18 FT X 2 PARTS)\*
  - 4 OBTAIN AND POSITION EACH "END FRAME", "DIAGONAL BR ACE" (PREPARATORY TO "SNAP ON"), AND PLATFORM \*(2
  - 5 APPLY PRESSURE TO "SNAP ON" "DIAGONAL BRACE" ON TO "END FRAME" \*8 "SNAP ONS"
- BT 185 1 ASSEMBLE OR DISASSEMBLE 5X6 FT SECTIONS OF PREFABR ICATED SCAFFOLDING AT GROUND LEVEL (THIS SEGMENT O
  - 2 ASSEMBLE OR DISASSEMBLE 5X6 FT SECTIONS OF PREFABR ICATED PIPE SCAFFOLDING TWO LEVELS HIGH (GROUND LE
  - 3 ASSEMBLE OR DISASSEMBLE5X6 FT SECTIONS OF PREFABRI CATED PIPE SCAFFOLD 3 LEVELS HIGH (TO ESTABLISH A
  - 4 ASSEMBLE OR DISASSEMBLE 5X6 FT SECTIONS OF PREFABR ICATED PIPE SCAFFOLDING 4 LEVELS HIGH (TO ESTABLIS
  - 5 ASSEMBLE OR DISASSEMBLE 5X6 FT SECTIONS OF PREFABR ICATED PIPE SCAFFOLDING 5 LEVELS HIGH (TO ESTABLIS
- BT 186 1 ASSEMBLE OR DISASSEMBLE 5X6 FT SECTIONS OF PORTABL E SCAFFOLDING AT GROUND LEVEL (THIS SEGMENT OF ASS
  - 2 ASSEMBLE OR DISASSEMBLE 5X6 FT SECTIONS OF PORTABL E SCAFFOLDING TWO LEVELS HIGH (GROUND LEVEL SHOWS
  - 3 ASSEMBLE OR DISASSEMBLE 5X6 FT SECTIONS OF PORTABL E SCAFFOLD 3 LEVELS HIGH (TO ESTABLISH A FORMULA G
  - 4 ASSEMBLE OR DISASSEMBLE 5X6 FT SECTIONS OF PORTABL E SCAFFOLDING 4 LEVELS HIGH (TO ESTABLISH FORMULA
  - 5 ASSEMBLE OR DISASSEMBLE 5X6 FT SECTIONS OF PORTABL E SCAFFOLDING 5 LEVELS HIGH (TO ESTABLISH A FORMUL
- BT 200 1 LOWER AND RAISE NECK \*REFERENCE: FOLDING GOOSENECK MODEL KFG-50T \*MANUFACTURED BY KALYN INCORPORATED
  - 2 DRIVING REQUIRED TO ATTACH AND DETACH TRACTOR TRAI
  - 3 DRIVE BULLDOZER (OR SIMILAR) ONTO LOWERED PLATFORM
  - 4 WALKING REQUIRED \*APPROX. 250 FT

- BT 201 1 LOWER AND RAISE PLATFORM \*REFERENCE: FOLDING GOOSE NECK MODEL KFG-50T \*MANUFACTURED BY KALYN INCORPOR
  - 2 DRIVING REQUIRED TO ATTACH AND DETACH TRACTOR TRAILER \*DONE TWICE FOR UNLOADING AND LOADING EQUIPMEN
  - 3 DRIVE BULLDOZER (OR OTHER HEAVY EQUIPMENT) ON/OFF LOWERED PLATFORM \*DONE TWICE FOR LOADING AND UNLOA
  - 4 WALKING REQUIRED \*APPROX. 400 FT \*DONE TWICE FOR U NLOADING AND LOADING\*400\*2
  - 5 TIE AND UNTIE HEAVY EQUIPMENT \*TWICE TIE, AND TWIC E UNTIE
- BT 202 1 POSITION CHAIN ON BARRIER \*POSITIONED TWICE
  - 2 SECURE CHAINS TO BARRIER \*SECURED TWICE
  - 3 LIFT, TURN BACKHOE, AND PLACE BARRIER
  - 4 TAKE OFF CHAINS \*DONE TWICE
  - 5 WALKING REQUIRED•